

Droga nr 671 plantowanie skarp w km 36+125 - 36+625 Zał. Nr 5

Kilometr	Hektometr	WYKOPIY				NASYPY			UWAGI
		Szerokość [m]	Średnia szerokość [m]	Odległość [m]	Powierzchnia [m²]	Szerokość [m]	Średnia szerokość [m]	Powierzchnia [m²]	
36	125	4,50				3,70			
36	127	6,50	5,50	2,00	11,00	3,00	3,35	6,70	
36	146,33	7,70	7,10	19,33	137,24	3,20	3,10	59,92	
36	150	7,90	7,80	3,67	28,63	3,20	3,20	11,74	
36	175	8,30	8,10	25,00	202,50	3,00	3,10	77,50	
36	200	9,80	9,05	25,00	226,25	3,00	3,00	75,00	
36	225	11,00	10,40	25,00	260,00	3,00	3,00	75,00	
36	250	10,70	10,85	25,00	271,25	3,00	3,00	75,00	
36	275	9,70	10,20	25,00	255,00	3,00	3,25	81,25	
36	298,76	8,60	9,15	23,76	217,40	3,50	3,70	87,91	
36	300	8,40	8,50	1,24	10,54	3,90	3,90	4,84	
36	325	4,30	6,35	25,00	158,75	3,90	4,10	102,50	
36	330,03	4,70	4,50	5,03	22,64	4,30	4,10	20,62	
36	350	5,40	5,05	19,97	100,85	3,90	3,75	74,89	
36	375	4,00	4,70	25,00	117,50	3,60	3,90	97,50	
36	400	2,40	3,20	25,00	80,00	4,20	4,60	115,00	
36	425	4,10	3,25	25,00	81,25	5,00	4,30	107,50	
36	450	4,60	4,35	25,00	108,75	3,60	4,00	100,00	
36	475	5,80	5,20	25,00	130,00	4,40	4,40	110,00	
36	500	5,80	5,80	25,00	145,00	4,40	4,10	102,50	
36	525	4,70	5,25	25,00	131,25	3,80	4,00	100,00	
36	550	4,50	4,60	25,00	115,00	4,20	4,20	105,00	
36	575	2,80	3,65	25,00	91,25	4,20	4,60	115,00	
36	600	2,90	2,85	25,00	71,25	5,00	4,85	121,25	
36	625	1,30	2,10	25,00	52,50	4,70	5,40	135,00	
			0,65			6,10	3,05		
			Razem:	500,00	3 025,80			1 961,62	