

Tabela robót ziemnych
Ścieżka rowerowa przy dr Nr 674 Sokółka Krynki w km 2+900 - 3+360

Zał. nr 1 do
przedmiaru robót

Kilometr	Hektometr	Powierzchnia		Średnia powierzchnia		Odległość	Objętość		Zużycie na miejscu	Nadmiar objętości		Suma algebraiczna	
		wykop +	nasyp -	wykop +	nasyp -		wykop +	nasyp -		wykop +	nasyp -	+	-
		m ²		m ²			mb	m ³		m ³	m ³		m ³
2	906,00	0,990	0,990										
				0,670	1,320	19,00	12,73	25,08	12,73		12,35		
	925,00	0,350	1,650										-12,35
				0,705	1,400	25,00	17,63	35,00	17,63		17,38		
	950,00	1,060	1,150										-29,73
			0,995	1,255	25,00	24,88	31,38	24,88		6,50			-36,23
			1,405	1,300	25,00	35,13	32,50	32,50	2,63				-33,60
3	0,00	1,880	1,240										
				1,325	1,170	25,00	33,13	29,25	29,25	3,88			
	25,00	0,770	1,100										-29,73
				0,870	0,880	25,00	21,75	22,00	21,75		0,25		
	50,00	0,970	0,660										-29,98
				1,370	0,340	25,00	34,25	8,50	8,50	25,75			
	75,00	1,770	0,020										-4,23
				2,475	0,035	25,00	61,88	0,88	0,88	61,00			
	100,00	3,180	0,050									56,775	
				2,305	0,250	25,00	57,63	6,25	6,25	51,38			
	125,00	1,430	0,450									108,150	
				1,255	0,670	25,00	31,38	16,75	16,75	14,63			
	150,00	1,080	0,890									122,775	
				0,835	1,100	25,00	20,88	27,50	20,88		6,63		
	175,00	0,590	1,310									116,150	
				0,600	1,635	25,00	15,00	40,88	15,00		25,88		
	200,00	0,610	1,960									90,275	
				0,555	2,135	25,00	13,88	53,38	13,88		39,50		
	225,00	0,500	2,310									50,775	
				0,510	2,300	25,00	12,75	57,50	12,75		44,75		
	250,00	0,520	2,290									6,025	
				0,500	2,140	25,00	12,50	53,50	12,50		41,00		
	275,00	0,480	1,990										-34,98
				0,475	2,470	25,00	11,88	61,75	11,88		49,88		
	300,00	0,470	2,950										-84,85
				0,415	2,860	25,00	10,38	71,50	10,38		61,13		
	325,00	0,360	2,770										-145,98
				0,275	2,580	25,00	6,88	64,50	6,88		57,63		
	350,00	0,190	2,390										-203,60
				0,195	2,575	3,00	0,59	7,73	0,59		7,14		
	353,00	0,200	2,760										-210,74
					1,380	7,00		9,66			9,66		
	360,00												-220,40
						454,00	435,07	655,47	275,82	159,25	379,65		