

**Droga nr 670 odc. Osowiec - Suchowola plantowanie skarp
w km 28+675 - 29+250**

Zał. Nr 4

Kilometr	Hektometr	Szerokość [m]	PLANTWANIE WYKOPOW			PLANTOWANIE NASYPÓW			UWAGI
			Średnia szerokość [m]	Odległość [m]	Powierzchnia [m ²]	Szerokość [m]	Średnia szerokość [m]	Powierzchnia [m ²]	
28	675	2,70				3,50			
			3,85	25,0	96,25		3,25	81,25	
28	700	5,00				3,00			
			5,10	25,0	127,50		3,00	75,00	
28	725	5,20				3,00			
			6,10	25,0	152,50		3,90	97,50	
28	750	7,00				4,80			
			7,50	25,0	187,50		4,40	110,00	
28	775	8,00				4,00			
			8,00	25,0	200,00		4,00	100,00	
28	800	8,00				4,00			
			7,50	25,0	187,50		4,35	108,75	
28	825	7,00				4,70			
			6,95	25,0	173,75		4,85	121,25	
28	850	6,90				5,00			
			6,85	13,6	93,16		4,50	61,20	
28	863,6	6,80				4,00			
			6,70	11,4	76,38		4,85	55,29	
28	875	6,60				5,70			
			7,55	25,0	188,75		5,35	133,75	
28	900	8,50				5,00			
			9,10	25,0	227,50		4,80	120,00	
28	925	9,70				4,60			
			6,95	25,0	173,75		4,00	100,00	
28	950	4,20				3,40			
			4,25	25,0	106,25		3,55	88,75	
28	975	4,30				3,70			
			4,30	25,0	107,50		3,65	91,25	
29	000	4,30				3,60			
			3,75	25,0	93,75		3,90	97,50	
29	025	3,20				4,20			
			3,60	19,5	70,20		3,95	77,03	
29	044,5	4,00				3,70			
			4,30	5,5	23,65		3,60	19,80	
29	050	4,60				3,50			
			5,50	25,0	137,50		3,25	81,25	
29	075	6,40				3,00			
			6,05	10,0	60,50		3,00	30,00	
29	085	5,70				3,00			
			5,25	10,0	52,50		3,00	30,00	
29	095	4,80				3,00			
			2,40	11,0	26,40		2,50	27,50	
29	106					2,00			
				13,3			2,25	29,93	
29	119,3					2,50			
				5,7			2,25	12,83	
29	125					2,00			
				25,0			3,00	75,00	
29	150					4,00			
				25,0			3,25	81,25	
29	175					2,50			
				14,9			3,50	52,15	
29	189,9					4,50			
				10,1			4,75	47,98	
29	200					5,00			
				6,1			6,20	37,82	
29	206,1					7,40			
				12,9			5,50	70,95	
29	219					3,60			
			0,85	6,0	5,10		2,80	16,80	
29	225	1,70				2,00			
			1,65	25,0	41,25		2,50	62,50	
29	250	1,60				3,00			
							1,50		
			RAZEM	575,0	2609,1				2 194,3
