

PRZEDMIAR ROBÓT

załącznik nr 3

Wykonanie nasypu - korekta łuku poziomego

Lokalizacja [km]	Projektowana niweleta [km]	P [m ²]	Pśr [m ²]	L [m]	V [m ³]
a	b	c	d	e	f
97+210,92	0+010,92	0,0000			
			0,1130	19,08	2,156
97+230,00	0+030,00	0,2260			
			0,6884	20,00	13,768
97+250,00	0+050,00	1,1507			
			1,6597	20,00	33,194
97+270,00	0+070,00	2,1686			
			1,9033	20,00	38,066
97+290,00	0+090,00	1,6380			
			1,1003	20,00	22,006
97+310,00	0+110,00	0,5626			
			0,2813	25,50	7,173
97+335,50	0+135,50	0,0000			
				Suma:	116,363